



广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH GROUP Co.,Ltd.

Material, Methodology and Inspection Technology for Structural Joints in Modular Integrated Construction

Dr. MA Xu

Guangdong Provincial Academy of Building
Research Group Co.,Ltd.

创新发展 服务社会

Contents

1	Background and Significance
2	Introduction
3	Standard requirements
4	Research on cementitious materials
5	Influence by grouting defects
6	Detecting techniques
7	Summary



广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH

创新发展 服务社会

创建美好和谐的共融美景

PART 01

Background and Significance


Prefabricated building

《Outline of the Modernization Development of Construction Industry》


2020, above 20% of new constructions will be Prefabricated building
 2025, above 50%



(a) 预制梁



(b) 预制梁柱节点



(c) 预制柱



(d) 预制楼梯



Government support policy

Solve current problems



Industrialization
 Fast construction speed
 Reduce labor
 Green
 Environment friendly
 Good overall benefit

Advantages

Joint connection

Connection method

- **Grout sleeve splicing**
- Grout anchor overlap
- Bolt connection
- Welding connection



The most common connection method




Above 60%

Grout sleeve splicing



Performance

Stability Safety Durability Seismic performance





广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH

创新发展 服务社会

创建美好和谐的共融美景

PART 02

Introduction

Grout sleeve splicing



Grout sleeve



Rebar



Cementitious grout



灌浆套筒

结构形式

全灌浆（整体式、分体式）

半灌浆（整体式、分体式）

材料

球墨铸铁



碳素结构钢

钢

低合金结构钢



加工方式

铸造

机械加工

切削加工

压力加工

滚压

锻造挤压

锻造滚压


Equivalent to cast-in-place

Good fluidity
 Early strength
 High strength
 Slight expansion

Grout sleeve


Half grout sleeve

Grout + Mechanical connection
 Prefabricated wall
 Prefabricated column





Complete grout sleeve

Grout + Grout connection
 Mainly
 Prefabricated beam






Application

Prefabricated concrete shear wall





Application

Prefabricated concrete frame beam



Application

Prefabricated concrete frame column




Installation process of frame column

Location



Gasket

Hoisting



Support

Installation process of frame column

Verticality



Airflow

Sealing



Grouting

Installation process of frame column



Mechanical grouting



Manual grouting

Influencing factors of connection quality




□ Connection material


□ Equipment and auxiliary

□ Connection method

Construction and management person



Influencing factors of grout sleeve splicing



Cementitious grout

Strength

Grouting defect

Grout sleeve

Diameter

Rebar

Anchor length

Related standards

《装配式混凝土建筑技术标准》 GB/T 51231-2016 **Architecture**




《装配式混凝土结构技术规程》 JGJ 1-2014 **Structure**

《钢筋机械连接通用技术规程》 JGJ107-2003 **Mechanical connection**

《钢筋连接用套筒灌浆料》 JG/T 408-2013 **Cementitious grout**

《钢筋连接用灌浆套筒》 JG/T 398-2012 **Grout sleeve**

《钢筋套筒灌浆连接应用技术规程》 JGJ 355-2015 **Application standard**





广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH

创新发展 服务社会

创建美好和谐的共融美景

PART 03

Standard requirements

Cementitious grout

Good fluidity

High strength

Early strength

Slight expansion

表 3.1.3-1 灌浆料抗压强度要求

Curing time 时间 (龄期)	抗压强度 (N/mm ²) Compressive strength
1d	≥35
3d	≥60
28d	≥85

Cementitious grout

表 3.1.3-2 灌浆料竖向膨胀率要求

项目	竖向膨胀率 (%) Vertical expansion rate
3h	≥ 0.02
Difference value 24h 与 3h 差值	0.02~0.50

表 3.1.3-3 灌浆料拌合物的工作性能要求

项 目		工作性能要求
Liquidity 流动度 (mm)	Initial 初始	≥ 300
	30min	≥ 260
泌水率 (%)		0

Grout sleeve

球墨铸铁灌浆套筒的材料性能 Cast iron

项 目	性能指标
Tensile strength 抗拉强度 σ_b /MPa	≥ 550
断后伸长率 δ_5 /%	≥ 5
球化率/%	≥ 85
硬度/ HBW	180~250



钢质机械加工灌浆套筒的材料性能 Steel machining

项目	性能指标
Yield Strength 屈服强度 σ_s (N/mm ²)	≥ 355
Tensile strength 抗拉强度 σ_b (N/mm ²)	≥ 600
断后伸长率 δ (%)	≥ 16



Rebar

Anchor length of Rebar \geq 8 times of rebar diameter



3.1.2 灌浆套筒应符合现行行业标准《钢筋连接用灌浆套筒》JG/T 398 的有关规定。灌浆套筒灌浆端最小内径与连接钢筋公称直径的差值不宜小于表 3.1.2 规定的数值，用于钢筋锚固的深度不宜小于插入钢筋公称直径的 8 倍。

表 3.1.2 灌浆套筒灌浆段最小内径尺寸要求

钢筋直径 (mm)	套筒灌浆段最小内径与连接钢筋公称直径差最小值 (mm)
12~25	10
28~40	15

The connection

- 3.2.2 钢筋套筒灌浆连接接头的抗拉强度不应小于连接钢筋抗拉强度标准值，且破坏时应断于接头外钢筋。
- 3.2.3 钢筋套筒灌浆连接接头的屈服强度不应小于连接钢筋屈服强度标准值。
- 3.2.4 套筒灌浆连接接头应能经受规定的高应力和大变形反复拉压循环检验，且在经历拉压循环后，其抗拉强度应符合本规程第 3.2.2 条的规定。



表 3.2.6 套筒灌浆连接接头的变形性能

项目		变形性能要求
对中单向拉伸	残余变形 (mm)	$u_0 \leq 0.10 (d \leq 32)$ $u_0 \leq 0.14 (d > 32)$
	Elongation (%)	$A_{sgt} \geq 6.0$
高应力反复拉压	残余变形 (mm)	$u_{20} \leq 0.3$
大变形反复拉压	残余变形 (mm)	$u_1 \leq 0.3$ 且 $u_8 \leq 0.6$

Centring

uniaxial tension

Off-center




图 2 偏置单向拉伸接头的钢筋偏置示意图
1—套筒内偏置的连接钢筋；2—灌浆料；3—灌浆套筒

High stress


repeated tension and compression

Large deformation

The connection


表 A.1.3 接头试件型式检验的加载制度

试验项目		Loading system 加载制度
单向拉伸		0→0.6 f_{yk} →0 (测量残余变形) →最大拉力 (记录极限抗拉强度) →破坏 (测定最大力下总伸长率)
高应力 反复拉压		0→(0.9 f_{yk} →-0.5 f_{yk}) →破坏 (反复 20 次)
大变形 反复 拉压	I 级	0→(2 ϵ_{yk} →-0.5 f_{yk}) →(5 ϵ_{yk} →-0.5 f_{yk}) →破坏 (反复 4 次) (反复 4 次)
	II 级	
	III 级	0→(2 ϵ_{yk} →-0.5 f_{yk}) →破坏 (反复 4 次)




单向拉伸

Uniaxial tension



高应力反复拉压

High stress
repeated tension
and compression



大变形反复拉压

Large deformation
repeated tension
and compression



广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH


创新发展 服务社会

创建美好和谐的共筑美好


PART 04

Research on cementitious materials

Cementitious grout




Cementitious grout





Early strength

High strength



Good fluidity

Cementitious grout



Mixing amount of expanding agent



Mixing amount of defoamer



Balance between
expansion and porosity

Cementitious grout


	Compressive strength / MPa			Fluidity / mm		Vertical expansion rate / %	
	1d	3d	28d	Initial	30min	3h	Difference 24h and 3h
Produced	38.6	71.8	102.6	347	315	0.2	0.04
Requirement	35	60	85	≥300	≥260	≥0.02	0.02~0.50



Cementitious materials for overlap joint

钢筋浆锚搭接连接接头用灌浆料性能要求

项 目		性能指标	试验方法标准
泌水率 (%)		0	《普通混凝土拌合物性能试验方法标准》 GB/T 50080
流动度 (mm)	初始值	≥ 200	《水泥基灌浆材料应用技术规范》 GB/T 50448
	30min 保留值	≥ 150	
竖向膨胀率 (%)	3h	≥ 0.02	《水泥基灌浆材料应用技术规范》 GB/T 50448
	24h 与 3h 的 膨胀率之差	0.02~0.5	
抗压强度 (MPa)	1d	≥ 35	《水泥基灌浆材料应用技术规范》 GB/T 50448
	3d	≥ 55	
	28d	≥ 80	
氯离子含量 (%)		≤ 0.06	《混凝土外加剂匀质性试验方法》 GB/T 8077



Cementitious materials for sealing

封浆料抗压强度、抗折强度要求

项目		技术指标
抗压强度 (MPa)	1d	≥ 30
	3d	≥ 45
	28d	≥ 65
抗折强度 (MPa)	28d	≥ 7

封浆料竖向膨胀率要求

项目		技术指标
竖向膨胀率 (%)	3h	≥ 0.02
	24h 与3h 差值	0.02~0.30

封浆料工作性能及氯离子含量要求

项目		技术指标
流动度 (mm)	初始	130~170
氯离子含量 (%)		≤ 0.03
泌水率 (%)		0






PART 05


Influence by grouting defects

Experiment

--- Making defects



Experiment --- Grouting




Experiment

--- Tensile test



Rebar



Grout sleeve splicing

Experiment

--- Results



No.	Anchor length of Rebar	Test result	No.	Anchor length of Rebar	Test result
1-1	8d	Rebar break	2-1	8d	Rebar break
1-2	7d	Rebar break	2-2	7d	Rebar break
1-3	5d	Rebar break	2-3	6d	Rebar break
1-4	3d	Rebar pullout	2-4	4d	Rebar pullout
1-5	7d	Rebar break	2-5	7d	Rebar break
1-6	5d	Rebar break	2-6	6d	Rebar break
1-7	3d	Rebar pullout	2-7	4d	Rebar pullout
1-8	8d	Rebar break			

Experiment

--- Results



No.	Anchor length of Rebar	Test result	No.	Anchor length of Rebar	Test result
1-1	8d	Rebar break	2-1	8d	Rebar break
1-2	7d	Rebar break	2-2	7d	Rebar break
1-3	5d	Rebar break	2-3	6d	Rebar break
1-4	3d	Rebar pullout	2-4	4d	Rebar pullout
1-5	7d	Rebar break	2-5	7d	Rebar break
1-6	5d	Rebar break	2-6	6d	Rebar break
1-7	3d	Rebar pullout	2-7	4d	Rebar pullout
1-8	8d	Rebar break			

Experiment


--- Results



No.	Anchor length of Rebar	Test result	No.	Anchor length of Rebar	Test result
1-1	8d	Rebar break	2-1	8d	Rebar break
1-2	7d	Rebar break	2-2	7d	Rebar break
1-3	5d	Rebar break	2-3	6d	Rebar break
1-4	3d	Rebar pullout	2-4	4d	Rebar pullout
1-5	7d	Rebar break	2-5	7d	Rebar break
1-6	5d	Rebar break	2-6	6d	Rebar break
1-7	3d	Rebar pullout	2-7	4d	Rebar pullout
1-8	8d	Rebar break			

Experiment

--- Results



Anchor length: at least **5d**
for this test condition

Influence

Grouting strength

·
·
·

No.	Anchor length of Rebar	Test result	No.	Anchor length of Rebar	Test result
1-1	8d	Rebar break	2-1	8d	Rebar break
1-2	7d	Rebar break	2-2	7d	Rebar break
1-3	5d	Rebar break	2-3	6d	Rebar break
1-4	3d	Rebar pullout	2-4	4d	Rebar pullout
1-5	7d	Rebar break	2-5	7d	Rebar break
1-6	5d	Rebar break	2-6	6d	Rebar break
1-7	3d	Rebar pullout	2-7	4d	Rebar pullout
1-8	8d	Rebar break			



广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH

创新发展 服务社会

创建美好和谐的共融美景

PART 06

Detecting techniques

The problems:

Sleeve grouting is not full

The strength of cementitious grout is low

The position deviation of reserved rebar is large

The embedded rebar is cut off

Cracks occur during lifting and transportation



.

.



Detecting is very important!

.



The related standards:

Shanghai: 《装配整体式混凝土建筑检测技术标准》
(DG/T 08-2252-2018)

Beijing: 《装配式混凝土结构工程施工与质量验收规程》
(DB42T 1225-2016)

Shandong: 《装配式混凝土结构现场检测技术标准》
(DB37/T 5106-2018)



Tianjing: 《装配式建筑预制混凝土构件质量与检验标准》
(DB/T29-245-2017)

Guangdong: 《装配式混凝土建筑工程施工质量验收规范》
(DBJ/T 15/71-2019)

·
·
·

Filling fullness of grouting

1) Pre-embedded detecting techniques



2) Nondestructive detecting techniques




图1 X射线胶片成像原理




At present,
no widely nondestructive
testing method is available
yet!

3) Partial-destructive detecting techniques

1) Pre-embedded sensor

Vibrational energy is different





空气中
Air




流体灌浆料中
Fluid grouting



固化灌浆料中
Solid grouting






饱满 (能量值0~150)




不饱满 (能量值151~255)


1) Pre-embedded sensor



出现漏浆





二次灌浆




1) Pre-embedded sensor

Need to be installed in advance!



2) Pre-embedded steel pull-off method



Need to be installed in advance!



The pull-off pressure is different

3) X-ray technique (CT)




图1 X射线胶片成像原理

Radiation problem!
 (at least 30 m away)


Thickness below 200mm is applicable for now.



a 射线机定位



b 墙体背面粘贴暗袋





射线源

平板探测器




控制器

4) Impact-echo method



Failure to effectively identify internal defects at present!

5) Ultrasonic method



Failure to effectively identify internal defects at present!

At present, the quality control is mainly focused on the construction process and manufacturing process.

Concealed work after construction is difficult to be effectively detected.

Effective detecting technique is lacking!

A combination of multiple detecting techniques

The development of new equipment and detecting techniques

A combination with machine learning , wireless transmission, 5G network ...



广东省建筑科学研究院集团股份有限公司

GUANGDONG PROVINCIAL ACADEMY OF BUILDING RESEARCH

创新发展 服务社会

创建美好和谐的共融美景

PART 07

Summary

- ◆ Prefabricated building will be more and more popular.
- ◆ Joint connection is the most important part, which influence the safety and durability of the building.
- ◆ Grout sleeve splicing is the most common connection method, but problems exist at present.
- ◆ The effective detecting techniques for grouting defects is lacking.
- ◆ We can make the cementitious grout with a good quality.

Thank you

Thanks For Your Attention !

Dr. MA Xu
maxuTUD@163.com