

The background image shows a construction site with a large crane lifting a concrete module. The crane is a lattice boom crane, and the module is a large, rectangular concrete structure. The sky is cloudy, and the overall scene is in grayscale, with the text overlaid in orange and blue.

Bringing a Wide Variety of Concrete MiC in Government Building


HKCI Annual Seminar 2022

Speaker: CHOY Chun-chuen, Assistant Director (Structural Engineering)

Architectural Services Department

Construction 2.0

Time to change



Construction 2.0

Time to change



Pillar 1: Innovation

The vision: The development of an Industry culture that embraces change, innovation and new technologies to drive forward productivity, efficiency and enhanced project delivery outcomes.



Pillar 2: Professionalisation

The vision: Improved professionalism of the Industry through step change increases in project leadership, project management, procurement capabilities and professional skills and practices within Government and the private sector, to deliver higher quality construction and built assets, combined with a first priority focus on safety, construction supervision and quality in the workplace.



Pillar 3: Revitalisation

The vision: Reinvigorating the appeal and benefits of joining the Industry to attract and nurture growing numbers of young and energetic talent to the workforce and increasing the agility at the individual, organisational and Industry levels.



Construction 2.0



Modular Integrated Construction (MiC)

Huge Construction Volumes

- Standardized and repeated design
- Minimized impact to environment

High Cost

- Reduce on-site labour cost
- Minimize abundancy and defects

Project Performance

- Assure construction quality
- Secure construction progress against unforeseen factors

Site Safety

- Reduce on-site works
- Enhance site safety

Productivity

- Prefabricate MiC in vast and remote factories
- Enhance production rate

Innovation

- Non-traditional construction approach
- Innovative connection details and construction material

ArchSD's MiC Construction Projects



Pak Shing Kok Disciplined Services Quarters



North Lantau Hospital Hong Kong Infection Control Centre



Quarantine Camps Projects



Residential Care Homes for the Elderly in Kwu Tung North



Kai Tak CIF/CTF



Penny Bay CIF/CTF (Ph5, 6A-6E)



Fire Station-cum-Ambulance Depot with Departmental Quarters and Facilities in Tseung Kwan O



Chinese Medicine Hospital


ArchSD's Concrete MiC Projects



Pak Shing Kok Disciplined Services Quarters



North Lantau Hospital Hong Kong Infection Control Centre



Quarantine Camps Projects



Residential Care Homes for the Elderly in Kwu Tung North



Kai Tak CIF/CTF



Penny Bay CIF/CTF (Ph5, 6A-6E)



Fire Station-cum-Ambulance Depot with Departmental Quarters and Facilities in Tseung Kwan O



Chinese Medicine Hospital

Procurement of MiC


Adoption of Design-and-Build (D&B) Contract for MiC

- ✓ **Only** design intent or reference drawing of MiC in tender;
- ✓ **Diverse MiC designs** and construction approach;
- ✓ **Buildability enhancement** in view of contractor's own resources;
- ✓ **Earlier inputs** in MiC development; &
- ✓ **Tighter teamwork** among all parties under D&B.

Tendering for Innovations

MiC Conducive Tendering

Weighting for Price and Technical Score



for D&B Projects

MiC Conducive Tendering

Standard marking scheme in accordance with DEVB TC(W) NO. 4/2014A

Quantitative Requirement



% CFA

% Types

Completeness

Design



Architectural

BS

Structure

Operation & maintenance

Technical Proposal



Method Statement

Programme

Quality Assurance Plan

MiC Conducive Tendering

Look for:

**BALANCE SOLUTION IN BOTH
TECHNICAL AND PRICE**

Completed Concrete MiC Project


Pak Shing Kok Disciplined Services Quarters

Pak Shing Kok Disciplined Services Quarters

- **Pilot Project**
- The **FIRST** high-rise concrete MiC building in Hong Kong
- 5 towers of 16-17 storey high (**648 nos.** of DQ units)
- **3726 nos.** of MiC Modules
- Commencement: Aug 2018
- Completion: Mar 2021
- **Design and Build Contract**
- Adoption of MiC proposed by contractor after contract award
- Construction Approach
 - Concrete MiC comprised of bearing and shear walls
 - In-situ cores and floor structure



MiC Modules and Extent




Typical Section



Legend

- Transfer Plate at 1/F
- MiC Modules
- In-situ structure

- Rest on rock
- G/F~1/F: Cast in-situ
- Small transfer plate at 1/F
- Typical floor: MiC at wings
- Roof : Cast in-situ



MiC Modules Section and Clear Height



Measured Indicators

- Skilled labours demand **reduced by 40-50%**
- Early completion **about 4 months** in advance of contract complete date
- In-situ concrete and rebar usage for a typical floor is **50% less** than the traditional project
- Site waste (landfill) **reduced by over 50%** compared to traditional in-situ construction
- Use of water and electricity on-site **reduced by around 70%**

On-going Concrete MiC Project

Residential Care Homes for the Elderly in Kwu Tung North


Residential Care Homes for the Elderly in Kwu Tung North

- 1 single block with 8 storeys, with 7-storey of MiC construction
- **1764nos.** of MiC Modules
- Commencement: Dec 2019
- Target Completion: Q4 2022
- **Design and Build Contract**
- Construction Approach
 - Concrete MiC comprised of permanent formworks for cast in-situ concrete work
 - In-situ cores and floor structure



MiC Modules and Extent

標準樓層平面圖
Typical Floor Plan




252 Units per floor
Total **1,764** Units

圖例 Legend



Structural Design of MiC Module

- MiC Modules shall be **permanent formwork** for Cast In-situ Reinforced Concrete Beam-Wall Frame
- Challenge - ensure concreting quality without demoulding



Quality Control of Self Compacting Concrete

- Quality control method:

- ✗ Ultrasonic Pulse Echo on Surface of Finished In-situ Concrete
- ✗ Sonic logging with Pre-installed Probes
- ✗ Inspection Openings on MiC Module
- ✓ Concreting by **Method Specification** Combined with **Control Tests/Inspections**

Method:

Self Compacting Concrete (SCC)
for concreting of Cast in-situ Beams / Walls



Control Tests / Inspections:

Step 1: Trial Panels




Step 2: Mock-up with Coring Test



Structural Connection between MiC



Casting by Self-Compacting Concrete




Up-coming Concrete MiC Projects

Projects Adopting Concrete MiC

- Concrete MiC will be widely adopted in up-coming projects of following building types:


- ☒ Staff Quarters
- ☒ Residential and Care Homes
- ☒ Schools
- ☒ Office
- ☒ Medical Facilities



- Among those projects adopting concrete MiC, the following projects are designated to introduce:
 - Fire Station-cum-Ambulance Depot with Departmental Quarters and Facilities in Tseung Kwan O
 - Redevelopment of Western Police Married Quarters

Fire Station-cum-Ambulance Depot with Departmental Quarters and Facilities in Tseung Kwan O

- 1 single block with 17 storeys, in which 12 storeys of MiC construction
- Around **640nos** of MiC Modules
- Commencement: May 2022
- Target completion: Q1/Q2 2025
- **Consultancy Contract**
- MiC is **Design-and-Build item**, where reference design of MiC unit is provided during tendering
- **Alternative MiC design** proposed by tenderer in tender return
- Construction Approach
 - Concrete MiC comprised of structural floor and walls
 - In-situ cores and floor structure of lobby/corridor




Redevelopment of Western Police Married Quarters



- 3 blocks with 28-29 storeys of MiC construction
- Tentative commencement: Q1 2023*
- Tentative completion: Q2 2027*
- **Design and Build Contract**
- Construction Approach
 - Concrete MiC comprised of permanent formworks for cast in-situ concrete work
 - In-situ cores and floor structure of lobby/corridor



Site Location Plan



Legends:

-  In-situ Podium & Basement
-  DQ Tower by MiC Modules with In-situ Corridor/ Lobby/ Core

*: Commencement and completion of D&B contract

What's Next?